



कपिलवस्तु नगरपालिका
KAPILVASTU MUNICIPALITY
नगर कार्यपालिकाको कार्यालय
OFFICE OF MUNICIPAL EXECUTIVE
तौलिहवा कपिलवस्तु
TAULIHAWA, KAPILVASTU
लुम्बिनी प्रदेश, नेपाल
LUMBINI PROVINCE, NEPAL



मिति : २०८१/०२/१०

पत्र संख्या : ०८०/०८१(पुर्वाधार)

चलानी नं.: १५३

विषय : दररेट पेश गर्ने सम्बन्धमा।

श्री निर्माण व्यवसायीज्युहरू

उपरोक्त विषयमा यस आ.व.०८०/०८१ मा तपसील बमोजिमको योजनाहरूको निर्माण कार्य सार्वजनिक खरिद ऐन २०६३ को दफा ४१ को (१) र नगरपालिकाको खरिद नियमावली २०७६ को नियम ८५ को उपनियम (१) बमोजिम सोभै खरिद(कोटेशन) विधिद्वारा गराउनु पर्ने भएकोले यस कार्यालयमा चालु आ.व.को लागि सुचीकृत निर्माण व्यवसायीहरूले BoQ मा उल्लेखित आइटमका कामहरू के कति दररेटमा गर्न सकिन्छ? BoQ मा भरी मिति २०८१ ज्येष्ठ २१ गते कार्यालय समय भित्र पेश गर्नको लागि यो सार्वजनिक सुचना जारी गरिएको ब्यहोरा जानकारीको लागि अनुरोध छ। साथै सोही नियमावलीको उपनियम(३) अनुसार एक आर्थिक वर्षमा एकै पटक वा पटक पटक गरी सीमाभन्दा बढी रकमको वा एउटै ब्यक्ति, फर्म, कम्पनी वा संस्थाबाट एक पटकभन्दा बढी सोभै खरिद गर्न सकिने छैन ब्यवस्था भएकोले सोही बमोजिम गर्नु हुन समेत जानकारीको लागि अनुरोध छ।

तपसील-

- १) बमनी गाउँ भित्रको सडक पी.सी.सी. तथा नाली निर्माण वडा नं.५(दोस्रो पटक)
- २) बिकुली फेदराहट सडक वडा नं.१०
- ३) कमर्डहल पछाडि जित बहादुरको घरदेखी चिन्नी कहारको घरसम्म माटो ग्राभेल वडा नं.१
- ४) राजेन्द्र पाण्डेको घरदेखी काली मन्दिरसम्म नाली निर्माण वडा नं.६
- ५) अस्पताल देखी शुशील के.सी.को घरसम्म नाली निर्माण वडा नं.६
- ६) केवलपुर जलैया सडक निर्माण वडा नं.८

मणेश प्रसाद अर्याल

प्रमुख प्रशासकीय अधिकृत

कपिलवस्तु नगरपालिका

KAPILVASTU MUNICIPALITY
Office of Municipal Executive
Taulihawa, Kapilvastu
Lumbini province

BILL OF QUANTITIES

१५/०२/०४
धनुस प्रशासकिय अधिकृत
F/Y: 2080/081

योजनाको नाम :-अस्पताल देखि शुसिल के.सीको घरसम्म नाली निर्माण कपिलवस्तु नगरपालिका वडा न ६
स्थान:-कपिलवस्तु नगरपालिका वडा न ६ गोबरी

Date:2081/02/04

SN	Descriptions of Works	Quantity	Unit	Rate in Figure	Rate in Words	Amounts	Remarks
1	Earthwork excavation/filling on Trench portion including compaction by haulage(out side Sources)	85.44	Cu.m				
2	Earthwork excavation in soft soil for drain and trenches including shoring, struting, bracing, sheeting and disposal upto 10 m and lift upto 1.5 m etc. all complete as per specification.By	45.00	Cu.m				
3	Dry Flat Brick Soling with sand sealing	135.00	sq.m				
4	Providing and placing machine mixed M10/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification.	13.50	Cu.m				
5	Providing and placing machine mixed M20/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification	22.03	Cu.m				
6	Providing and fitting 75mm Dai HDPE pipe (NS or IS)mark including all complete work	10.00	Rm				
7	Providing , Preparing and Installing form work including necessary supports and removing after completion for foundation and footings (a) using timber (soft wood) - Class F1 finish. [1804, 1805]	244.40	sq.m				
8	Providing and laying Reinforcement (diameter above 8 mm and upto 16 mm) including cutting, bending, binding, fixing in position and lead 30m. etc. all complete as per specification and	728.96	kg				
9	Back filling Filter material behind structure including levelling	20.40	Cu.m				
10	providing and fitting Project sign board	1.00	No				
					Total Aount		
					Add VAT @ 13% of Total		
					Grand Total with VAT		

Submitted by:

Bidder's Name:

Proprietor

Adress:

contact No:

Signature and Date:

Firm's Stamp: