



कपिलवस्तु नगरपालिका
KAPILVASTU MUNICIPALITY
नगर कार्यपालिकाको कार्यालय
OFFICE OF MUNICIPAL EXECUTIVE
तौलिहवा, कपिलवस्तु
TAULIHAWA, KAPILVASTU
लुम्बिनी प्रदेश, नेपाल
LUMBINI PROVINCE, NEPAL



कपिलवस्तु नगरपालिकाको कार्यालय
तौलिहवा, कपिलवस्तु
लुम्बिनी प्रदेश
२०७३

पत्र संख्या : ०८०/०८१(पुर्वाधार)
चलानी नं.: २९६३

मिति : २०८१/०२/१०

विषय : दररेट पेश गर्ने सम्बन्धमा।

श्री निर्माण व्यवसायीज्युहरु

उपरोक्त विषयमा यस आ.व.०८०/०८१ मा तपसील बमोजिमको योजनाहरुको निर्माण कार्य सार्वजनिक खरिद ऐन २०६३ को दफा ४१ को (१) र नगरपालिकाको खरिद नियमावली २०७६ को नियम ८५ को उपनियम (१) बमोजिम सोभैं खरिद(कोटेशन) विधिद्वारा गराउनु पर्ने भएकोले यस कार्यालयमा चालु आ.व.को लागि सुचीकृत निर्माण व्यवसायीहरुले BoQ मा उल्लेखित आइटमका कामहरु के कति दररेटमा गर्न सकिन्छ? BoQ मा भरी मिति २०८१ ज्येष्ठ २१ गते कार्यालय समय भित्र पेश गर्नको लागि यो सार्वजनिक सुचना जारी गरिएको ब्यहोरा जानकारीको लागि अनुरोध छ। साथै सोही नियमावलीको उपनियम(३) अनुसार एक आर्थिक वर्षमा एकै पटक वा पटक पटक गरी सीमाभन्दा बढी रकमको वा एउटै ब्यक्ति, फर्म, कम्पनी वा संस्थाबाट एक पटकभन्दा बढी सोभैं खरिद गर्न सकिने छैन ब्यवस्था भएकोले सोही बमोजिम गर्नु हुन समेत जानकारीको लागि अनुरोध छ।

तपसील-

- १) बभनी गाउँ भित्रको सडक पी.सी.सी. तथा नाली निर्माण वडा नं.५(दोस्रो पटक)
- २) विकुली फेदराहट सडक वडा नं.१०
- ३) कभर्डहल पछाडि जित बहादुरको घरदेखी चिन्नी कटारको घरसम्म माटो ग्रामेल वडा नं.१
- ४) राजेन्द्र पाण्डेको घरदेखी काली मन्दिरसम्म नाली निर्माण वडा नं.६
- ५) अस्पताल देखी शुशील के.सी.को घरसम्म नाली निर्माण वडा नं.६
- ६) केवलपुर जलैया सडक निर्माण वडा नं.८

(Signature)

गणेश प्रसाद अर्याल
प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत



Kapilvastu Municipality

Office of Municipal Executive

Taulihawa, Kapilvastu, Lumbini Province

Bill Of Quantities (BOQ)



प्रमुख प्रशासकिय अधिकृत

F/Y:-2080/081

योजनाको नाम : बिकुली फेदराहट सडक बडा नं. १०


योजना स्थल : कपिलवस्तु नगरपालिका १०

SL.	Item Description	Unit	Quantity	Rate(NRS)	Rate In Words	Amount(NRS)	Remarks
1	Erthwork in Excavation of Foundation of Structures in ordinary soil	Cu.m	6.05				
2	Providing, laying, spreading, watering and compacting embankment with borrow material in layer not exceeding 150mm including haulage as per drawing and Technical Specifications (Machine Means)	Cu.m	11.58				
3	Providing and laying Dry stone Masonry for soling	Cu.m	1.44				
4	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means)	Cu.m	9.60				
5	Providing and applying 12.5 mm thick plaster with cement mortar (cement:sand 1:4) on brickwork in structure as per drawing and Technical Specification	Sq.m	37.60				
6	Providing and Painting two coats after filling the surface with synthetic enamel paint in all shades on concrete/ plaster surfaces as per Drawing and Technical Specifications. Unit = sqm (For 10 sqm)[SS-1501]	Sq.m	37.60				
7	Providing and Installation of Retroreflective delineator post (900mm height, 50mm dia) all complete as per Drawing and Technical Specifications	Nos	100.00				
8	Providing and Fixing of road stud 100x 100 mm, die-cast in aluminum, resistant to corrosive effect of salt and grit, fitted with lenses reflectors, installed in concrete or asphaltic surface by drilling hole 30 mm upto a depth of 60 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per Specification clause 1505, Cats Eye	Nos	700.00				

9	Providing and Fixing of road stud 100x 100 mm, die-cast in aluminum, resistant to corrosive effect of salt and grit, fitted with lenses reflectors, installed in concrete or asphaltic surface by drilling hole 30 mm upto a depth of 60 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per Specification clause 1505, Solar Cats Eye	Nos	24.00				
10	Providing and fixing of plastic speed breaker of size 250x350x50 mm, yellow black packing colour including two reflectors to each 250mm length with cement filling at bottom to get load capacity of 30 tonne, installed in concrete or asphaltic surface by drilling hole 30 mm upto a depth of 60 mm and bedded in a suitable bituminous grout or epoxy mortar, all as per Drawing and Technical Specifications. Speed Breaker [1505]	Rm	5.00				
11	Supplying and fitting of 1.20mx0.90m retro reflective settlement information board with 50mm ms black pipe post, 2mm thick ms sheet and fixing into the M15 grade concrete with nut bolt all complete as per instruction of engineer.	Nos	2.00				
12	Providing and laying of PCC Grade M10(1:3:6 for nominal mix) in foundation complete as per Drawing and Technical Specifications (By Machine)	Cu.m	1.63				

Form Name:-

Stamp:-



Sign:-