



कपिलवस्तु नगरपालिका
KAPILVASTU MUNICIPALITY
नगर कार्यपालिकाको कार्यालय
OFFICE OF MUNICIPAL EXECUTIVE
तौलिहवा, कपिलवस्तु
TAULIHAWA, KAPILVASTU
लुम्बिनी प्रदेश, नेपाल
LUMBINI PROVINCE, NEPAL



पत्र संख्या : ०८०/०८१(पुर्वाधार)

चलानी नं.: ३०६९

मिति : २०८१/०२/२५

विषय : दररेट पेश गर्ने बारे ।

श्री सम्बन्धित व्यवसायीज्युहरु

उपरोक्त विषयमा यस नगरपालिका अर्न्तगत तपशील बमोजिमका योजनाहरुको निर्माण कार्य सार्वजनिक खरिद ऐन २०६३ को दफा ४१ को (१) र नगरपालिकाको खरिद नियमावली २०७६ को नियम ८५ को उपनियम (१) बमोजिम सोभै खरिद(कोटेशन) विधिद्वारा गराउनु पर्ने भएकोले यस कार्यालयमा चालु आ.व.को लागि सुचीकृत निर्माण व्यवसायीहरुले के कति दररेटमा गर्न सकिन्छ ? संलग्न BoQ मा भरी मिति २०८१ ज्येष्ठ २८ गते कार्यालय समय भित्र खास बन्दी गरी पेश गर्नु हुन अनुरोध छ ।

तपशील-

१) हैण्डपम्प जडान वडा नं.५


राजेश कुमार शैनी
इन्जिनियर

बोधार्थ-

श्री सुचना प्रविधि शाखा Website तथा Facebook मा Upload गरिदिनुहुन ।



कपिलवस्तु नगरपालिका
नगर कार्य पालिकाको कार्यालय
तौलिहवा, कपिलवस्तु
लुम्बिनी, प्रदेश



BILL OF QUANTITY

Procurement Method.: Direct Purchase

ब.क्र.सं.:

योजनाको नाम: हेण्डपाइप खरिद तथा जडान बडा नं.१ अर्न्तगत
सम्पन्न गर्नु पर्ने म्याद: असार १५, २०८१

S.n.	Description of Works	Unit	Quantity	Rate (NPR)		Total Amount (NPR)	Remarks
				In Figures	In Words		
A	Sludging of hole by manual method with 1.5" dia G.L pipe for Handpump Installation by hand Sludging method						
1	0 - 20	r/mtr	180.00				
2	20 - 30	r/mtr	90.00				
3	30 - 40	r/mtr	81.00				
B	Procurement of pipes and accessories						
1	Supplying and fitting of CI Hand Pump Head 4 no. Nepali including accessories all complete as per NS standrad	Set	9.00				
2	48mm uPVC pipe(BS3505 Class-E) Panchakanya or equipvalent	R.M.	351.00				
3	Supplying and fitting of 1.5" dia GI Pipe (Medium Class) 0.90 long threaded on both side	R.M.	8.10				
4	Supplying and fitting of 48mm PVC Ribbed Well Screen 2m long	R.M.	18.00				
5	Supplying and fitting of 48mm PVC Sand Trap 1.0m long with conical end plug	R.M.	9.00				
6	Supplying and fitting of 48 mm PVC M/F Threaded Adaptor	PC	9.00				
7	Teflon Tape	Roll	9.00				
8	Concreting work(1:2:4) for fixing of G.I.Pipe	Cu.M.	0.36				
				Sub-Total :			
				VAT 13%			
				Total with Vat			

Sign:

Seal

Name of Firm:

Contact no.: