



कपिलवस्तु नगरपालिका
KAPILVASTU MUNICIPALITY
नगर कार्यपालिकाको कार्यालय
OFFICE OF MUNICIPAL EXECUTIVE
तौलिहवा, कपिलवस्तु
TAULIHAWA, KAPILVASTU
लुम्बिनी प्रदेश, नेपाल
LUMBINI PROVINCE, NEPAL



पत्र संख्या : ०८०/०८१(पुर्वाधार)

मिति : २०८१/०२/२४

चलानी नं.:

विषय : दररेट पेश गर्ने बारे ।

श्री सम्बन्धित व्यवसायीज्युहरु

उपरोक्त विषयमा यस नगरपालिका अर्न्तगत तपशील बमोजिमका योजनाहरुको निर्माण तथा आपूर्ति कार्य सार्वजनिक खरिद ऐन २०६३ को दफा ४१ को (१) र नगरपालिकाको खरिद नियमावली २०७६ को नियम ८५ को उपनियम (१) बमोजिम सोभै खरिद(कोटेशन) विधिद्वारा गराउनु पर्ने भएकोले यस कार्यालयमा चालु आव.को लागि सुचीकृत व्यवसायीहरुले उक्त समानको Specification बमोजिमको सामानहरु के कति दररेटमा उपलब्ध गराउन सकिन्छ ? संलग्न BoQ मा भरी मिति २०८१ ज्येष्ठ २७ गते कार्यालय समय भित्र खास बन्दी गरी पेश गर्नु हुन अनुरोध छ ।

तपशील-

- १) वडाको आवश्यक स्थानमा माइलेज तथा संकेत बोर्ड जडान वडा नं.१
- २) वडाको विभिन्न स्थानमा संकेत बोर्ड जडान वडा नं.१
- ३) डेलिभरी पाइप खरीद वडा नं.७
- ४) विष्णु उपाध्यायको घरदेखी सिकन्दर तेली र शिसुपाल मौर्याको घर हुदै हुलाकी सडकसम्म पक्की नाली निर्माण पुरानो हाटबजार वडा नं.१

गणेश प्रसाद अर्याल
प्रमुख प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत


बोधार्थ-

श्री सुचना प्रविधि शाखा Website तथा Facebook मा Upload गरिदिनुहुन ।



Kapilvastu Municipality
Office of Municipal Executive

Bill Of Quantities (BOQ)



प्रमुख प्रशासकिय अधिकृत
F/Y:-2080/081

योजनाको नाम : बिष्णु उपाध्यायको घर देखी सिकन्दर तेली र शिशुपाल मौर्याको घर हुदै हुलाकी रोड सम्म पक्की नाली निर्माण पुरानो हाटबजार

SL.	Item Description	Unit	Quantity	Rate(NRS)	Rate In Words	Amount(NRS)	Remarks
1	Earthwork						
1.01	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cu.M	39.55				
1.02	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters, Dismantling Stone Masonry	Cu.M	3.12				
2	Sub-Base,Base						
	Supplying & place naturally found or quarry sieved loose gravel material including levelling all completes as per Specifications.	Cu.M	3.21				
3	Concrete work						
3.01	Providing and laying of PCC (Grade M 10) in Foundation complete as per Dwaring and Technical Specifications	Cu.M	3.21				

पाना नं १

3.02	Providing and laying of PCC (Grade M 20) in Sub Structure complete as per Drawing and Technical Specifications. (Height upto 5m)	Cu.M	15.22			
4	Steel Reinforcement					
	Providing and laying fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	KG	780.96			
5	Formwork					
	Providing, Preparing and installing form work including necessary supports and removing after completion for Foundation and footings (Class F1 finish)	Sq.M	129.80			
6	Project Information Board	LS	1.00			

प्रा.स. (२)