



कपिलवस्तु नगरपालिका
नगर कार्यपालिकाको कार्यालय
तौलिहवा, कपिलवस्तु
लुम्बिनी प्रदेश, नेपाल



प.सं.: २०८१/८२ (पूर्वाधार)

लुम्बिनी प्रदेश
२०७३

मिति: २०८२/०२/०८

च.नं.: २६२८

श्री निर्माण व्यवसायीज्यूहरु

विषय: दररेट पेश गर्ने बारे सूचना ।

उपरोक्त विषयमा यस नगरपालिका अन्तर्गत तपशिल बमोजिमका निर्माण कार्यहरु सार्वजनिक खरिद ऐन २०६३ को दफा ४१ र यसपालिकाको खरिद नियमावली २०७६ को नियम ९५ को उपनियम (१) बमोजिम सोझै खरिद (कोटेशन) विधिद्वारा गराउनु पर्ने भएकोले यस आ.व.को लागि सूचीकृत निर्माण व्यवसायीहरु यस कार्यालयबाट प्रकाशित सूचना बमोजिमको सूचीमा दररेट भरी मिति २०८२ वैशाख ११ गते कार्यालय समय भित्र निवेदन पेश गर्नु हुन अनुरोध छ ।

राजेश कुमार शैनी

इन्जिनियर

इन्जिनियर

तपशिल:

क्र.स.	योजनाको नाम	लागत अनुमान (भ्याट सहित)
१	सिचाई तथा खानेपानी बोरिंग जडान	रु. ८,८६,३६४.४५
२	ह्यान्ड पम्प जडान वडा नं २	रु. १०,००,०००.००
३	अधुरो वडा कार्यालय निर्माण वडा नं ९	रु. ९,९९,३४३.१५
४	सडक इन्टर लकिंग ब्लक वडा नं ९	रु. ७,९९,५५५.८५
५	वडा कार्यालय भित्र ढलान र स्वास्थ्य चौकी भित्र ढलान वडा नं ५	रु. १०,००,०००.००
६	जगदीशपुर बनबाटिकालाइट जडान	रु. ४,९४,६२३.२३

बोधार्थ-

श्री सूचना प्रविधि शाखा-कार्यालयको Facebook app र Website मा अपलोड गरिदिनु हुन ।



कपिलवस्तु नगरपालिका
नगर कार्यपालिकाको कार्यालय
तौलिहवा, कपिलवस्तु
लुम्बिनी, प्रदेश



प्रमुख प्रशासकिय अधिकृत

BILL OF QUANTITY

कार्यालय वा परियोजनाको नाम:

योजनाको नाम र कार्यान्वयन हुने स्थल: वडा नं. ९ बनबाटिका भित्र लाइट जडान
सम्पन्न हुने अनुमानित अवधि: २०८२ ज्येष्ठ


आर्थिक वर्ष: २०८१/०८२
बजेट उप शीर्षक नं:

S.n.	Description of Works	Unit	Quantity	Rate (NPR)		Total Amount (NPR)	Remarks
				In Figures	In Words		
1	Earthwork in excavation in fondation in hard and gravel mix soil with lead 30m. for base of garden pole all complete.	Cu.M.	0.88				
2	Plain cement concrete PCC(1:2:4) in foundation all complete.	Cu.M.	0.50				
3	Fromwork for concrete all complete.	Sq.M.	6.72				
4	Supplying and fixing of alumunium Base plate for TMT Bolt	Set	6.00				
5	Fitting and fixing of 16mm TMT(L6") 2.5ft pillar churi 20mm 4 nut bolt system all complete	Nos.	64.00				
6	Supplying and fixing of 3.5-4.00 meter top post pole made of cast iron with connection terminal box. (post design as per client)	Nos.	16.00				
7	Supply and Installation of 40-60 watt LED hanging street light with with voltage range 110v-270v, day night sensor (PF≥0.9, IP≥66, CRD≥70, SPD-10KVA) Di Cast Iron housing, disfuser 85mm, milk color hanging die) all complete as per instruction and specification.	Set	16.00				
8	Supplying and fixing of two core 10.0mm ² alumunium conductor wire all complete	R.M.	100.00				
9	Supplying and fixing of 2 core 1.5mm copper conductor wire all complete	R.M.	50.00				
10	Supplying and installation of 6-32amp. single pole MCB all complete	Set	16.00				
				Sub-Total :			
				VAT 13% of Item A			
				Total with Vat			

Bidders Name:
Sign:
Stamp:



कपिलबस्तु नगरपालिका
नगर कार्यपालिकाको कार्यालय
तालिहवा, कपिलबस्तु
लुम्बिनी प्रदेश, नेपाल
Abstract of Cost (AOC)



प्रमुख प्रशासकीय अधिकृत



आर्थिक वर्ष: २०८१/०८२
बजेट उप शीर्षक नः

कार्यालय वा परियोजनाको नाम: नगरसभाबाट स्वीकृत योजना
योजनाको नाम र कार्यान्वयन हुने स्थल: सडक इन्टरलकिंग ब्लाक वार्ड नं ९ जलैया गाउ सडक इन्टरलकिंग ब्लाक
सम्पन्न हुने अनुमानित अवधि: २०८२ ज्येष्ठ मसान्तसम्म

क्र.सं.	काम/सेवाको विवरण आइटम	एकाइ	परिमाण	दर अंकमा (रुपैयाट बारेक)	दर अक्षरमा	जम्मा रकम	कैफियत
A	General						
1	Clearing of grass, removing roots breaking sods, levelling the surface and disposal 10 m.[201]	Sq.m	60.00				
2	Backfilling in layers in foundation pits,trenches with common excavated material etc including compaction and watering etc complete,lead 10 m a) Depth of foundation upto 1.5m[908]	Cu.m	4.00				
3	Earthwork excavation in soft soil for drain and trenches including shoring, struting, bracing, sheeting and disposal upto 10 m and lift upto 1.5 m etc. all complete as per specification. [Manual][905]	Cu.m	1.96				
5	Providing and placing manually mixed M15/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing	Cu.m	1.96				
6	Steel Reinforcement	K.g	100.74				
7	Providing , Preparing and Installing form work including necessary supports and removing after completion for foundation and footings	Sq.m	32.64				
8	Supply And Laying of (Fancy Paver A Size11"x8" - Leather finish Multi Colour(sealed) with compressive Strength M25 or Above made by automated plant)Interlock Concrete Block Tile 60mm Thick Heavy over 50mm thick Stone Dust all complete as per drawings.	Sq.m	204.00				
					Total		
					Vat १३%		
					Grand Total		



कपिलवस्तु नगरपालिका
नगर कार्यपालिकाको कार्यालय
तौलिहवा, कपिलवस्तु
लुम्बिनी प्रदेश, नेपाल
BILL OF QUANTITY

प्रमुख प्रशासकीय अधिकृत

आर्थिक वर्ष: २०८१/०८२

बजेट उप शीर्षक नः

कार्यालय वा परियोजनाको नाम: नगरसभाबाट स्वीकृत योजना
योजनाको नाम र कार्यान्वयन हुने स्थल: अघुते वार्ड कार्यालय बेवस्थापन
सम्पन्न हुने अनुमानित अवधि: २०८२ ज्येष्ठ मसान्तसम्म

क्र.सं.	काम/सिवाको विवरण	एकाइ	परिमाण	दर अंकमा (भ्याट बाहेक)	दर अंशरमा (भ्याट बाहेक)	जम्मा रकम	कैफियत
	आइडम						
1	Clearing of grass, removing roots breaking sods, levelling the surface and disposal 10 m.[201]	Sq.m	60.00				
2	Backfilling in layers in foundation pits,trenches with common excavated material etc including compaction and watering etc complete,lead 10 m a) Depth of foundation upto 1.5m[908]	Cu.m	3.20				
3	Earthwork excavation in soft soil for drain and trenches including shoring, strutting, bracing, sheeting and disposal upto 10 m and lift upto 1.5 m etc. all complete as per specification. [Manual][905]	Cu.m	45.75				
4	Supply & place naturally found or quarry sieved loose gravel material including levelling all completes as per Specifications.	Cu.m	1.20				
5	Providing and placing manually mixed M15/40 cement concrete for the foundation and footing etc. including compaction, curing, testing and lead 30m. etc. all complete as per specification and drawing	Cu.m	7.81				
6	Steel Reinforcement	K.g	302.14				
7	Providing, Preparing and installing form work including necessary supports and removing after completion for foundation and footings	Sq.m	75.34				
8	Providing and laying brick masonry in manual mixed cement mortar including preparation of mortar as per specification, lead 30 m.	Cu.m	11.08				
9	12.5mm thick cement sand plaster in (1:4) ratio on wall of good finish including racking the joint, wetting of surfaces & curing the work all complete.	Sq.m	246.50				
10	Making and fitting different shape and size of MS Angle including red oxide paint all complete(20*20*3)	K.g	28.80				
11	GI barbed wire-fencing work	R.m	300.00				
12	2 coats of plastic emulsion paint paint of approved colour over 1 coats of primer Painting over properly cleaned surface all complete	Sq.m	230.00				
13	Supply And Laying of (Fancy Paver A Size11"x8" - Leather finish Multi Colour(sealed) with compressive Strength M25 or Above made by automated plant)Interlock Concrete Block Tile 60mm Thick Heavy over 50mm thick Stone Dust all complete as per drawings.	Sq.m	94.08				
					Total		
					vat @13%		
					Grand Total		



कपिलवस्तु नगरपालिका
नगर कार्यपालिकाको कार्यालय
तौलिहवा, कपिलवस्तु
लुम्बिनी प्रदेश, नेपाल
कार्यालय कोड नं.: ८०५४९४०९३००

प्रमुख प्रशासकिय अधिकृत



BILL OF QUANTITIES

आ.ब २०८१/०८२

कार्यक्रम / योजनाको नाम: वडा नं. ६ वडा कार्यालय बाकी काम

कार्यक्रम / योजनाको नाम र कार्यान्वयन हुने स्थल: क.व.न.प.-६ सेमरी

SN	Descriptions of Works	Quantity	Unit	Rate in Figure	Rate in Words	Amounts	Remarks
1	Earth work excavation for foundation in soft soil including all necessary works	28.98	Cu.m				
2	Flat Brick soling with sand sealing including compaction	58.17	Cu.m				
3	providing ,mixing and placing manual mixed M10 grade cement concrete for the foundation including curing all complete as per specification.	0.57	Cu.m				
4	providing ,mixing and placing manual mixed M15 grade cement concrete for the foundation including curing all complete as per specification.	8.37	Cu.m				
5	providing ,cutting, bending, binding and placing reinforcement bar including curing all complete as per specification.	446.47	kg				
6	providing and laying Brick masonry work in (1:4) cement sand mortar it including all necessary works	3.68	Cu.m				
7	Providing , Preparing and Installing form work including necessary supports and removing after completion for works	45.42	Sq.m				
8	12.5mm thick (1:4) cement sand mortar plastering work including mixing laying scaffolding curing all necessary works	18.30	Sq.m				
9	3mm thick neat punning work	18.30	Sq.m				
10	providing and fitting 63mm dia (UPVC) NS vent pipe	2.00	Rm				
11	Earth filling from front side, levelling, and side development work	1.00	Ls				
					Total Amount		
					Add VAT @ 13% of Total		
					Grand Total with VAT		

Submitted by:

Bidder's Name:

Proprietor

Address:

contact No:

Signature and Date:

Firm's Stamp:



कपिलवस्तु नगरपालिका
नगर कार्य पालिकाको कार्यालय
तौलिहवा, कपिलवस्तु
लुम्बिनी, प्रदेश
२०७३

प्रमुख प्रशासकिय अधिकृत

BILL OF QUANTITY

कार्यक्रमको नाम:-नगरपालिका आनुदान वडास्तरीय

योजनाको नाम:-खानेपानी हेण्डपाइप जडान(वार्ड नॉ ,२)

S.n.	Description of Works	Unit	Quantity	Rate (NPR)		Total Amount (NPR)	Remarks
				In Figures	In Words		
A	Sludging of hole by manual method with 1.5" dia G.I. pipe for Handpump Installation by hand Sludging method						
1	0 - 20	r/mtr	500.00				
2	20 - 30	r/mtr	250.00				
3	30 - 42.2	r/mtr	305.00				
B	Procurement of pipes and accessories						
1	No. 6 C.I Nepali Handpump (22 to 23 Kgs) including accessories all complete, NS Standard.	Set	25.00				
2	48mm uPVC pipe(BS3505 Class-E) NS Or IS	R.M.	1,030.00				
3	Supplying and fitting of 1.5" dia GI Pipe (Medium Class) 0.90 long threaded on both side	R.M.	22.50				
4	Teflon Tape	Roll	25.00				
Sub-Total :							
VAT 13%							
Total with Vat							

Sign:

Seal

Name of Firm:



कपिलबस्तु नगरपालिका
नगर कार्यपालिकाको कार्यालय
तौलिहवा, कपिलबस्तु
लुम्बिनी प्रदेश, नेपाल

प्रमुख प्रशासकिय अधिकृत

Bill of Quantities

आर्थिक वर्ष: २०८०/०८१

कार्यालय वा परियोजनाको नाम: सिचाई तथा खानेपानी बोरिंग जडान

योजनाको नाम र कार्यान्वयन हुने स्थल: क व न पा -२

सम्पन्न हुने अनुमानित अवधि: २०८२ असार मसान्त

क्र.सं.	काम/सेवाको विवरण आइटम	एकाइ	परिमाण	दर		जम्मा लागत	कैफियत
				अंकमा	अक्षरमा		
१	२	३	४	५	६	७=४*५	८
A.	Drilling works						
1	Drilling of pilot hole by std. bit above 7 5/8" to 9 7/8" dia. All complete	Meter	124.50				
2	Electric logging, Plotting & Design of well Assembly. All Complete.	Job	2.00				
3	Reaming of pilot hole by std. bit above 9 7/8" and below 13 3/4" dia. All complete	Meter	124.50				
4	Lowering of Pipe assembly as per design .All Complete	Meter	124.50				
5	Well development by compressor	Hrs	32.00				
	Sub-Total						
B.	Pipe & Other Aecessories						
6	Supply & Packing of Pea gravel 4-6 mm size.All Complete.	Cu.m.	7.83				

7	4" Dia UPVC pipe (B.S.3505, NS or IS mark, class E pipe)	Meter	124.50				
8	4" UPVC Screen (Screen Making Charge on UPVC)	Meter	12.00				
	Sub-Total						
C.	Miscellaneous Works						
a	Preparation of mud.pit (1.5m *1.5m*1.5m)	m ³	6.75				
b	Site Clearance (Cutting uprooting and disposal of grass, with light compaction leveling and cleaning the site (15m *15m)	m ²	450.00				
c	Platform preparation for rig, compressor and pump (a) 1*5m*2m (b) 1*5m*2m © 1*5m*4	m ²	20.00				
	Sub-Total						
	Total(A+B+C)						
	VAT@13%						
	Grand Total						